

MMSD Planned Construction or Services Bids*
April 3, 2023- March 31, 2024

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
TBD	Contact Basin Drain Valve Replacements at SSWRF - Replace drain valves south of the chlorine contact basins	2	2023
S06045C14	Digester Sphere wet blasting and epoxy coating - Furnish all labor, equipment, and materials necessary to wet abrasive blast and re-coat the exterior surface of the two digester spheres located at the SSWRF. The entire surface of the sphere exterior, support legs, and X-brace leg supports shall be prepared and coated. The Contractor shall prepare the surface by wet abrasive blast with crushed glass or other suitable non-metallic abrasive to remove all mold/mildew, chalk, loose coatings, as well as provide an evenly profiled, dull surface. Upon completion of surface preparation, the surface shall be coated with one primer epoxy coating, and two finish urethane coatings.	2	2023
C05055C01	N 35th and Roosevelt Improvements - The scope includes construction of 3,000 feet of 48-inch sewer via microtunneling, 6 new manholes, various local sewers, abandonment of 6,700 feet of 42" sewer, and abandonment of BS0503 pump station.	2	2023
I06001C01	NS-12 Collector System Improvements - The scope includes construction of 2,600 feet of 84-inch sewer via tunneling, modifications to existing diversion structure, and 500 feet of 120-inch x 72-inch box culvert.	2	2023
C02012C01	Oak Creek Partial Lateral Replacement Project: Rehab 5 private laterals and a portion of OC sewer. All sagging due to MIS construction methods. Contract to include: residential coordination, erosion control, restoration and traffic control	2	2023
J04079C01	Dryer Tire Replacement - Replacing Dryer tires and trunnions and performing alignments on this equipment.	2	2023
J06090C01	Clarifier Electrical Isolation at JIWRf - On all primary and secondary clarifiers: electrically isolate the metallic components inside the clarifiers from all external metal)	2	2023
C06023C01	VA Grounds MIS Relocation - The scope includes construction of ~1,720 feet of 24-inch diameter MIS via open cut construction. This new MIS will replace existing 24-inch diameter MIS that will be abandoned by this project (approximately 600 feet). The scope also includes slip lining ~385 feet of existing 42-inch diameter MIS.	2	2023
C98067C01	Conveyance Gate Replacement - The scope includes replacement of nine sluice gates and one gate stem at four conveyance locations.	2	2023
S02015C02	Basin Drain Sampling System - Provide new water quality sampling equipment with associated plumbing, electrical, instrumentation, controls and HVAC work.	2	2023
W20028C01	Western Milwaukee Phase 2B Levee and Floodwall - The scope includes soil remediation, 1,500 feet of quarry stone streambank, 1,700 feet of earthen levee, 1,350 feet of concrete floodwall, 6,400 feet of storm sewer, ~ 2,000 feet of water line, communication duct, street reconstruction, and vegetation restoration of 7 acres.	2	2023
J06081C01	MCC Replacements at JIWRf - The scope replaces 31 motor control centers (MCCs), one load center unit substation (LCUS) and one motor control substation. Some MCCs will be replaced with new MCCs, while others will be replaced with new switchboards as the existing MCCs no longer contain starters or other motor control equipment. The scope also includes door relocation, HVAC improvements, and other electrical room modifications related to NFPA 820.	2	2023
C02014E01	Condition Assessment - Pipe 42406 - Cleaning and CCTV of 54-inch MIS. The information obtained will be used to develop an approach for rehabilitation.	2	2023
C98059C06	Large Diameter Sewer Cleaning - Cleaning and debris disposal for several sections of large diameter MIS	2	2023
TBD	KK04 Media Replacement - Replace the activated carbon media for this ISS inlet structure	2	2023
S06045C10	SSWRF Secondary Clarifier Concrete Repairs - Replace a defective section of concrete deck over the Mixed Liquor Channel in Battery 2.	2	2023
J06080C17	Scum Concentrator Overhaul at JIWRf - Replace all drivetrain components, chains, and flights. Epoxy coat the interior of the decant tank.	2	2023
S06044C02	FRP Tank Inspections at JIWRf and SSWRF - Inspect and repair twenty fiberglass reinforced plastic chemical storage tanks.	2	2023
J06080C19	JIWRf Multiple UPS Replacement - Replace five UPS units.	2	2023
G98022C01	Fresh Coast Green Highways - Install green infrastructure under the Becher Street Overpass between 4th and 5th Street on Becher Street.	2	2023
M01040C02	13th Street Monitoring Van Garage - Replace cabinetry and ceiling in water quality equipment room. Remove existing coating system on concrete garage floor and replace with new epoxy coating system.	2	2023
MCRR1563	Trackmobile Transmission Rebuild - repair transmission to stop leak and restore useful life	2	2023
MCRR 1604	DD ASU 20, 24, 25 Replacement - replace ASU's in DD control or computer rooms	2	2023
MCRR 1587	DD Add-Back Screws Replacement - replace 12 add back screw conveyors	2	2023

MMSD Planned Construction or Services Bids*

April 3, 2023- March 31, 2024

Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
MCRR 1451C	DD Dryers A, B, C, F Blade Replacements - Replace blades in 2 dryers	2	2023
MCRR 1556	SS Primary Clarifiers #1, #8 and #12 Repairs - Replace flights, chain and sprockets.	2	2023
MCRR 1606	JI IPS Wet Well #3 Liner Replacement - Replace the PVC lining system in the wet well.	2	2023
MCRR 1608	SS Digester Gallery Concrete Repairs - Remove and replace delaminated concrete on the ceiling and beams in the digester gallery.	2	2023
G98022C01	Becher Street Overpass - This project will install various types of green infrastructure underneath the Becher Overpass between 4th and 5th Street along Becher Street.	2	2023
M98001C01	Milwaukee Estuary AOC Dredged Material Management Facility - The scope includes construction of a 42-acre double sheet pile containment area with bulk barrier to provide a 1.9 million cubic yard storage facility for contaminated dredged material removed from Milwaukee estuary. Construction also includes offloading platform, water management systems and access paths.	3	2023
TBD	ISS Pump Overhauls at JIWRP - Overhaul the ISS pumps at Jones Island	3	2023
J04070C03	Phase 2 Slide Gate Upgrades at Dewatering and Drying Facility - Replacement of isolation gates and associated chutes on the recycle bin feed and wet recycle screw conveyors.	4	2023
W24010C01	State Fair Culvert PE and Phase 1 - The scope includes the rehabilitation of approximately 9,500 LF of corrugated metal pipe using trenchless rehabilitation methods.	4	2023
J06080C20	JIWRP Turbine Bldg. MCC Repairs - Replace gas compressor skid motor starters.	4	2023
J06089C01	Flow Meter Replacement at JIWRP - Replace seven large flow meters throughout JIWRP, including influent, ISS pumpout, and disinfection flow meters.	4	2023
W20033C01	Menomonee River Levee System Accreditation - The scope includes levee and floodwall freeboard raises at four locations, including approximately 500 feet of floodwall raises, 1,900 feet of levee raises, and miscellaneous floodwall structural rehabilitation. The project will include tree removals near the levee system, and vegetation restoration.	1	2024
C03014C01	Greenfield Park and Underwood Creek Pump Stations Upgrades - The scope includes rehabilitation of process mechanical, electrical and control systems at two conveyance pump stations	1	2024
W10004C01	Estabrook Falls Fish Passage - Remove bedrock from the bed of the Milwaukee River to improve hydraulic conditions for passage of native fish. Restore vegetation.	1	2024
	*All schedules are estimates and subject to change. This list will be updated quarterly.		