

MMSD Planned Construction or Services Bids*			
January 1, 2024 - December 31, 2024			
Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
J06090C01	Clarifier Electrical Isolation at JIWRf - On all primary and secondary clarifiers: electrically isolate the metallic components inside the clarifiers from all external metal.	1	2024
G98025C01	Mineral Street Overpass - Install green infrastructure under the Mineral Street Overpass from West Scott Street to West Virginia Street and from 5th Street to 9th Street.	1	2024
M01048C01	Security Improvements - The scope includes upgrades to the security camera, access control, and visitor management systems at Jones Island WRF, South Shore WRF, HQ/Lab and 13th Street Facilities.	1	2024
J06080C22	Mixed Liquor Channel Rehabilitation - This scope replaces the concrete diffuser containers within the Southern-Eastern Mixed Liquor Channel.	1	2024
C98059C11	Collection System Point Repairs - This scope addresses 5 locations where sectional liners are required within the collection system (12-inch, 18-inch, 30-inch, 36-inch and 48-inch).	1	2024
W98008C0(TBD)	2024 - 2026 Watercourse Maintenance Invasive Species Management, 30th St. North & East Basin - Contract consists of vegetation maintenance including, turf mowing, snow removal, and non-routine maintenance such as tree and debris removal.	1	2024
S04038C03	Digesters 4 and 12 Cleaning at SSWRF - Clean Digesters 4 and 12, inspect the interiors, and make repairs to piping and concrete as necessary.	1	2024
W98006P16	Reforestation and Wetland Restoration - Tree procurement and delivery of 2,850 trees/shrubs for Mequon Nature Preserve reforestation project.	1	2024
N/A	Digester Gas Spheres Condition Assessment - Conduct a survey of the condition of the digester gas storage spheres and their associated structural components and piping at the South Shore Water Reclamation Facility.	1	2024
C02012C01	Oak Creek Lateral Project - Restore five 6-inch lateral crossings and one 8-inch City of Oak Creek sewer crossing over an MIS to their original vertical alignments. Additionally traffic control, driveway apron repair and natural landscapes rehab are included.	1	2024

MMSD Planned Construction or Services Bids*			
January 1, 2024 - December 31, 2024			
Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
S06038C(TBD)	Thickened Primary Sludge Pipelines 1 and 2 Replacement at South Shore Water Reclamation Facility - Replace two, 6-inch diameter thickened primary sludge pipelines.	1	2024
C03014C01	Greenfield Park and Underwood Creek Pump Stations Upgrades - The scope includes rehabilitation of process mechanical, electrical and control systems at two conveyance pump stations.	2	2024
J06081C01	MCC Replacements at JIWRP - The scope replaces 31 motor control centers (MCCs), one load center unit substation (LCUS) and one motor control substation. Some MCCs will be replaced with new MCCs, while others will be replaced with new switchboards as the existing MCCs no longer contain starters or other motor control equipment. The scope also includes door relocation, HVAC improvements, and other electrical room modifications related to NFPA 820.	2	2024
C98066E02	H2S Priority Sites Condition Assessment - Advanced condition assessment of various MIS sites to determine the extent of wall loss on concrete pipe that has been exposed to high levels of hydrogen sulfide.	2	2024
G98023(TBD)	Fresh Coast Green Communities - Greenprint will have 3-5 BIDs for GI construction projects in 2024. The District will help promote their advertisements.	2	2024
W98006(TBD)	Reforestation and Wetland Restoration - Tree procurement and planting of 1,000 trees for Forest Home Cemetery & Arboretum.	2	2024
W10004C01	Milwaukee River Habitat Enhancement Estabrook Falls - Remove bedrock from the bed of the Milwaukee River to improve hydraulic conditions for passage of native fish and restore vegetation.	3	2024
W20033C01	Menomonee River Levee System Accreditation - The scope includes levee and floodwall freeboard improvements along with storm sewer closure improvements near the Hart Park levee system.	3	2024
S02017C01	Blower Branch Pipe Replacement - Replace the four buried 30-inch blower branch pipes from the Blower and Generator Building 326 to the buried 60/90-inch main air header, to patch areas of corrosion on the buried 60/90-inch main air header adjacent to the blower branch pipes, and to replace the 30-inch blower branch pipe isolation valves and expansion joints inside Building 326. The new buried piping will be carbon steel with external coating. Removal of an existing coal tar enamel coating with asbestos as needed to complete the branch pipe replacement and main air header patching, work to maintain the existing cathodic protection system through and after construction, and surface restoration.	3	2024
J02012C01	West Plant Air Header Rehabilitation - The scope will rehabilitate mechanical joints on the existing 48-inch, 54-inch, and 6--inch diameter cast iron pipe using internal seals and external clamps.	3	2024

MMSD Planned Construction or Services Bids*			
January 1, 2024 - December 31, 2024			
Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
J04076C01	Compressed Air System Upgrades - The scope will replace nine existing compressors in three buildings with two new centralized compressor systems in two buildings; replace two compressors and remove seven compressors. The scope also includes new air dryers, storage tanks, mechanical piping, electrical, instrumentation and controls.	3	2024
J04077C01	Odor Control at Equalization and Blend (E&B) Facility - The scope will add a new treatment stage for Equalization and Blend (E&B) tank air emissions. The improvements include a new biological scrubber located upstream of a new carbon adsorption unit, odorous air piping, and a booster fan, if needed. The E&B building will be modified to add a vertical extension to the odor control room above the existing roof line, including new walls, removable roof, and door access. Associated improvements include HVAC, drain piping, lighting, electrical, instrumentation and controls work.	3	2024
S02018C01	RAS Pumps Replacement - Replace eight return activated sludge (RAS) pumps and motors. Mechanical work includes replacement of pump suction and discharge piping, expansion joints, check valves, isolation valves and piping supports. Electrical work includes replacement of the pump motors, variable frequency drives, 480V switchboard breakers, and associated conduit and wiring. Control work includes replacement of RAS pump instrumentation and transmitters. Other work includes removal of concrete, providing new concrete equipment pads, masonry, doors, finishes and painting.	3	2024
S06050C01	HVAC Systems Improvements in Buildings 378 & 380 - The scope includes replacing HVAC equipment at the Administration Building (378) and Maintenance Building (380). The scope may include replacing the acoustical drop ceiling and lens covers for existing light fixtures.	4	2024
C98065C01	Separate Sewer Outfall Abandonment - Project includes the design and construction for the decommissioning and abandonment of nine Sanitary Sewer Overflow Outfall sites. Decommissioning and abandonment includes: removing all equipment, including gates, stoplogs, monitoring equipment, telemetry, and I&C. Remove electrical service as necessary to decommission the site. Properly bulkhead and abandon the outfall pipe per state standards/requirements.	4	2024
<i>*All schedules are estimates and subject to change. This list will be updated quarterly.</i>			