

MMSD Planned Construction or Services Bids*			
July 1, 2025 - June 30, 2026			
Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
C02012C01	10th Avenue Lateral Replacement - Construction to replace portions of 5 residential sanitary sewer laterals and 1 municipal sanitary sewer by open-cut construction in City of Oak Creek.	3	2025
C98059C11	Collection System Point Repairs - The contract scope consists of sectional cured-in-place pipe (SCIPP) liners to be installed at two locations to address the pipe holes identified: 12-inch within Pipe 04613 on West Blue Mound Road, and 48-inch within Pipe 10909 on South Kinnikinnic Avenue. Work includes mobilization, traffic control, and cleaning and televising of the sewers upon completion of the SCIPP installation.	3	2025
J01019C01	Jones Island Force Main Improvements - Construction includes rehabilitation of 72" and 78" diameter force main at Jones Island WRF. Contract scope also includes cleaning force main, spot repairs of force main at 5 locations and steel surface recoating ~177' of force main.	3	2025
S06038C35	Thickened Primary Sludge Pipelines 1 and 2 Replacement at South Shore Water Reclamation Facility - The contract scope consists of the replacement of two 6-inch Thickened Primary Sludge (TPS) Pipelines from Tunnel 13 to the Building 353 Digester Gallery; a distance of approximately 850 lineal feet. The TPS pipeline replacements include the relocation of small sections of 8-inch W1 and 8-inch W3 piping and removal of approximately 250 lineal feet of existing and previously decommissioned 8-inch W3 piping. The TPS pipeline installation includes all bends, valves, pipe hangers, and fittings required to achieve the piping alignment shown on the Plans.	3	2025
TBD	CCO Temporary Office Space - Scope includes leasing a modular office building for temporary installation at JIWRF while Building 280 remodeling is underway, concluding when new office space is established (approximately 2 year lease). Leased building will include office space for 12-13 employees, two bathrooms, kitchenette, and small common space. A separate, on-call construction task order will be issued to establish connections to plant utilities, etc.	3	2025

MMSD Planned Construction or Services Bids*			
July 1, 2025 - June 30, 2026			
Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
TBD	Barb Wire Installation, 32nd & Hampton - Install barded wire security lines on top of existing chain link fence at the MMSD facility located at N. 32nd St and W Hampton Ave. Work includes but not limited to installation of barbed wire support arms and all necessary components for the successful installation of the barbed wire on the existing chain link fence.	3	2025
TBD	Fence Installation, 35th and W. Courtland Ave - Work will include but not limited to the installation of 2 3/8" driven galvanized fence post along with the installation of 8" high galvanized fence with tension top wire. Approximately 150 LF of fence material is required along with associated fence post and top wire.	3	2025
TBD	Flooring Removal & Replacement, 32nd & Hampton - Work will include but not limited to removal of existing 2 1/2" thick by 2"x4" wooden endgrain block flooring. Once removed, work shall consist of sealing of existing concrete subfloor and installation of new concrete flooring to raise the elevation of the subfloor to match existing flooring elevations.	3	2025
TBD	Floodwall Crack Repair, Milwaukee County Grounds & Valley Park - This work will include various crack repair to District owned concrete floodwall located at various locations. Various crack repairs will be detailed in the construction plans and specifications.	3	2025
S06044C03	2026/2027 FRP Tank Inspections - Scope includes inspecting 9 FRP tanks at South Shore and 9 FRP tanks at Jones Island. The tanks are used for sodium hypochlorite, sodium bisulfite, ferric chloride, and glycol storage at the water reclamation facilities. Upon inspection, the Engineer will work with the Contractor to determine what repairs are needed (if any) to the fiberglass reinforced plastic tank interior and/or exterior.	3	2025

MMSD Planned Construction or Services Bids*			
July 1, 2025 - June 30, 2026			
Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
S01013C02	Primary Clarification System Improvements - Construction of new clean water research center at South Shore WRF. Contract scope includes foundation excavation, earth retention, structural concrete, masonry building, roofing, building HVAC mechanical, building electrical services, instrumentation and controls, facility solar panels, and installation of owner-procured process mechanical equipment.	3	2025
M01045C01	Pelagos Slip Modifications at Headquarters Dock - Construction of jib crane, electrical improvements, and site lighting work to improve access to MMSD's research vessel (Pelagos). Contract also includes replacement of dock decking with new PVC deck materials.	3	2025
MCRR 1763	Backdraft Dampers for D&D Odorous Air Fans 2 and 4 - Fabricate and install round backdraft dampers for OD air fans 2 and 4	3	2025
C03014C01	Greenfield Park and Underwood Creek Pump Stations Upgrades - Construction includes pump rehabilitations, replacement of mechanical, electrical, and control systems, and new backup generators.	3	2025
C03013C01	Oklahoma Avenue MIS Capacity Improvements - Construction of ~ 3,300' of new 48" diameter sewer via microtunneling. Contract also includes relocation of local utilities, abandonment of a pump station, and associated site restoration.	3	2025

MMSD Planned Construction or Services Bids*			
July 1, 2025 - June 30, 2026			
Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
W20033C01	Menomonee River Levee System Improvements - Construction scope includes levee and floodwall freeboard improvements along with storm sewer closure improvements integral with or near Hart Park levee system. Includes approximately: 1,800' of earthen levee raise, 750' of reinforced concrete floodwall raise, 100' of 30" diameter storm sewer with flap gate, 72" diameter storm sewer new structure with internal flap gate, 90' of 8" diameter sanitary sewer, 1,800' of paved maintenance drive, and site restoration.	4	2025
J04057C01	Milorganite® Dryer Exhaust Duct Header and Damper Replacement - Construction for removal and replacement of ~750' of existing 36" to 96" diameter stainless dryer exhaust ducting, installation of owner-procured guillotine dampers and owner-procured butterfly dampers, and associated electrical instrumentation and controls work.	4	2025
S01015C01	Grit Equipment Replacement - Construction scope includes replacement or rehabilitation of the following equipment in Preliminary Treatment Facility: Grit slurry cups, dewatering escalators (snails), grit/screenings conveyors, primary sludge screenings conveyor, and winches for grit load out containers.	4	2025
MCRR 1717	Diversion Chamber DC0103 & DC0603 Repairs - Scope involves replacement of equipment in the DC0103 and DC0603 conveyance sites. The equipment primarily includes electrical and control panels, a hydraulic power unit, a nitrogen support system, forced air ventilation, and other elements affected by high levels of H2S evident at the site. Project will also implement some simple measures to increase resistance of replacement equipment to H2S exposure at the site, including new hazardous environment conduit seals and cabinet positive pressure elements.	4	2025
C02013C01	Oak Creek Southwest MIS Extension - Construction of ~5,300' of 24" diameter Metropolitan Interceptor Sewer via two-pass tunneling construction from West Oakwood Road to Racine County line. Contract also includes provisions for future municipal connections, pavement and site restoration.	4	2025

MMSD Planned Construction or Services Bids*			
July 1, 2025 - June 30, 2026			
Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
W40019C01	Jackson Park Service Yard - Construction scope includes demolition, salvage, and recycling of structures at Jackson Park Service Yard, which consists of ~6,800 SF of building area on a 1.1- acre site. The work includes disconnection and abandonment of utilities, removal of asbestos-containing materials and other regulated materials prior to demolition, salvage and recycling of structures, placement of fill, regrading to maintain site surface drainage patterns, and surface restoration.	4	2025
M01044C01	HQ and Lab Buildings Remodel - The scope includes the full remodel of MMSD HQ Building Floors 1 - 4.	4	2025
TBD	On-Call Sewer Televising & Cleaning - The scope includes on-call service sewer televising and cleaning in the conveyance system and potentially at the Jones Island WRF and South Shore WRF.	4	2025
TBD	South Shore Water Reclamation Facility Electrical Switchgear Procurement - Procurement of electrical switchgear and transformer equipment to be installed by a future contract. Electrical equipment is required to tie future solar panel electrical generating equipment into existing South Shore WRF electrical system.	1	2026
S04029C01	Digester Mixing II - Replace mixing systems in 2 anaerobic digesters, convert 1 storage tank to active digester, provide building and equipment modifications to voluntarily comply with NFPA 820, and upgrade network communication infrastructure for digester gallery. Clean 2 digesters and 1 storage tank; structural and piping restoration; equipment removals, new mixing systems; new sludge feed, sludge withdrawal, hot water piping, heat exchange system, and gas collection system for converted digester; electrical improvements; replacement of withdrawal pumps and isolation valves for 3 storage tanks; removal of the abandoned digester gas purifiers; fill open space after purifiers are removed with roof slab; modifications to existing digester control system and new fiber optic cable runs.	1	2026

MMSD Planned Construction or Services Bids*			
July 1, 2025 - June 30, 2026			
Contract # (if known)	Contract Name and Scope	Advertise Quarter	Advertise Year
C05041C04	Basin H MIS Remediation and Sewer Rehabilitation - Construction scope includes rehabilitation of MIS by installing joint seals and remediating longitudinal cracks in pipe segments, and rehabilitating manholes located in Basin "H" of Central MIS sewer system. Project also includes cleaning and removal of sediment from subject sewers.	1	2026
G98032C01	Holt Avenue Overpass - Green Highways - The project will consist of the construction of bioretention basins, native vegetation and landscaping, site grading, surface restoration, underground storm sewer piping and structures, installation of rock-lined channels, and a five-year vegetation maintenance contract for the native vegetation. As design progresses, more details can be released.	1	2026
J06083C01	HVAC System Improvements - Construction to replace and update heating, ventilation and air conditioning (HVAC) equipment and controls in Buildings 234 (RAS Pump Station), 235 (WAS Pump Station), 243 (Chemical Unloading Facility), 256 (Thickening Facility), 257 (Equalization and Blend Facility), 258 (Dewatering and Drying Facility), 263C (Inline Pump Station), 279 (Operations Building) and 289A (Powerhouse - boiler room addition).	2	2026
C04005C01	Martha Washington/Highland Area MIS Improvements - Construction includes ~12,000' of sewer rehabilitation with cured-in-place pipe lining in sewers 15" to 27" diameter, cured-in-place lateral lining, sewer cleaning, sewer televising, ~350' of 24" diameter sewer installed by open cut methods, 2 manholes, flow control of wastewater, traffic control, sewer abandonment, and site restoration.	2	2026
W42003C01	43rd Street Ditch - Lincoln Ave Culvert Replacement - Construction scope includes replacing 375' of failing corrugated metal culverts along W. Lincoln Avenue with cast-in-place and pre-cast multi-cell reinforced concrete box culverts, including cast-in-place junction and outfall structures.	2	2026
<i>*All schedules are estimates and subject to change. This list will be updated quarterly.</i>			