

Technical Standard - CCTV

CCTV completed as part of the work for the Pipe Check program shall meet the following requirements:

- A footage counter must be accurate, calibrated, and shown on the video display.
- The property address, municipality, and if it is a pre or post rehabilitation video shall be shown at the beginning of the video. (a small whiteboard is often used)
- The camera should be set so 100% of the pipe circumference is visible during televising. Televising rate shall not exceed 30 feet per minute.
- The video shall maintain continuous visibility throughout the entire length of lateral televising of the post lateral replacement or rehabilitation video. Videos where the camera is underwater or the lens has become contaminated will be required to be re-done.
- A pan and tilt camera preferred and recommended for all recordings submitted to the Pipe Check program.
- Each lateral television inspection shall begin when the Contractor has successfully set-up the equipment at the mainline / lateral connection or sanitary manhole / lateral connection, and or an internal / external lateral access structure.
- Contractor shall complete the televising and recording by means of returning the televising equipment to the launching point (pull back).

For all lateral lining work, a CCTV recording shall be provided to the Pipe Check program. The video shall be uploaded to t4 Vault and a hyperlink the video shall be included in the notes section of the invoice application.

All pre-repair or replacement (lateral) CCTV inspections shall be recorded and provided to the homeowner.